



SMART CITY THIRUVANANTHAPURAM LIMITED

SCTL/GEN/2703/2023/AM-C/13

Date: 27.11.2023

REQUEST FOR QUOTATION

Smart City Thiruvananthapuram Limited is inviting quotations for the "*Reconstruction of median at Killipalam Junction*".

Scope of Work

Reconstruction of 20 m in length median which includes concrete works , excavation, demolition, plastering and painting works of the median at Killipalam junction .Detailed description of items to be executed as scheduled below.

General Conditions:

1. Work shall be completed within 14 days from the date of LOA.

Payment Terms:

1. Payment shall be made as per actual measurement at site as per schedule quoted.

Sealed Quotations have to be submitted to Smart City Office on or before 01st December 2023, 11:00 AM. Quotations received after 01st December 2023,11.00 AM will not be entertained.

Sd/-

Chief Executive Officer
Smart City Thiruvananthapuram Limited






SMART CITY THIRUVANANTHAPURAM LIMITED

Quotation

Sl. No	Description	Qty	Unit	Rate	Amount
1	Earth Work Earth work in excavation of foundation of structures as per drawing and technical specification,including setting out,construction of shoring and bracing,removal of stumps and other deleterious matters , dressing of sides and bottom,backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work Ordinary soil-Manual Means-(Depth upto 3M)	0.300	cum		
2	Dismantling work Dismantling of existing structures like culverts ,bridges,retaining walls and other structures comprising of masonry,cement concrete,wood work,steel work,including T&P and scaffolding wherever necessary ,sorting the dismantled material,disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 meters Cement Concrete Grade M-15 & M-20-By Mechanical Means	2.561	cum		
3	Concrete Works Plain cement concrete 1:3:6 nominal mix in foundation with crushed stone aggregate 40mm nominal size mechanically mixed,placed in foundation and	1.281	cum		





SMART CITIES MISSION

Smart City Ministry of Housing and Urban Affairs, Government of India

SMART CITY THIRUVANANTHAPURAM LIMITED

	compacted by vibration including curing for 14 days.				
4	Shuttering Works Centering and shuttering including strutting, propping etc. and removal of formwork for: Foundations, footings, bases for columns	18	Sqm		
5	Plastering Work 12mm cement plaster of mix 1:4 (1 cement : 4 fine sand)	16	Sqm		
6	Painting Works Painting two coats after filling the surface with synthetic enamel paint in all shades on new plastered concrete surfaces	16	Sqm		
	Total				
	Total in words :				

Note: The rates for the work shall be quoted exclusive of GST.

